



**PUBLIC WORKS DEPT**

# H.A.W.K. Signals TCHS & Windmill Point

**Project Manager:**  
Heath Stocton, P.E.  
(772) 344-4239  
hstocton@cityofpsl.com

**Design:**  
Culpepper & Terpening, Inc.

**Construction:**  
American Lighting and Signalization, Inc.

**Schedule:**  
Design is Complete  
Construction to be Complete in the Fall of 2015

**Description:**

A High intensity Activated crossWalk (HAWK) signal provides a protected pedestrian crossing as a way to increase safety. It is used only for pedestrian crossings. It does not control traffic on side streets. When you wish to cross the street, you push a button activating the HAWK signal. A flashing yellow light warns drivers approaching the crosswalk of a pedestrian wishing to cross. The flashing yellow light is followed by a solid yellow light telling drivers to prepare to stop. The signal then changes to a solid red for drivers to stop at the intersection. Drivers can continue through the intersection without stopping until the button is again activated.

This project includes construction of three (3) High-Intensity Activated Crosswalk Signals.

Two signals will be located on SW Darwin Blvd. adjacent to Treasure Coast High School and one signal will be located on SW Tunis Avenue adjacent Windmill Point Elementary. Additional signage and striping will also be provided.

**Progress:**

All design is complete. Contractor has been selected and pre-construction meeting has been held. Mast arms have been ordered and are currently awaiting receipt. Drilled shaft foundations have been completed as well as conduit installation for fiber optic, signal, and power cables. Installation of Mast Arms is expected in early August, 2015.

**Current Conditions:** In Construction (Foundations have been installed Mast Arms have been ordered)

**Location:** Darwin Blvd & Tunis Ave

